

Sample

January 10, 2017

We at Jayson Global Roofing Inc. would like to thank you for the opportunity to submit a quotation for the following roofing specifications.

Job Name: Sample Residence

Job Code: L

Job Address:

Job Number: Re-roof Existing House

Supply and Install: Standard nail pattern

Price:

IKO Cambridge AR Laminate shingles 15/LT warranty	\$4,658.00	<input type="checkbox"/>	or	\$49.45	*Monthly
IKO Cambridge IR (impact rated) Laminate shingles 15/LT warranty	\$6,482.00	<input type="checkbox"/>	or	\$68.81	*Monthly
IKO Hip & Ridge Plus segmented fibreglass strip shingles used as capping (included)	\$429.00	<input type="checkbox"/>	or	\$4.55	*Monthly
IKO Ultra HP SBS pre-formed high profile ridge capping (manufacturer recommended)	\$429.00	<input type="checkbox"/>	or	\$4.55	*Monthly
MALARKEY Highlander Laminate Shingles 10/30 year warranty	\$6,324.00	<input type="checkbox"/>	or	\$67.13	*Monthly
MALARKEY Legacy SBS Laminate Shingles 15/50 year warranty	\$7,286.00	<input type="checkbox"/>	or	\$77.34	*Monthly
MALARKEY Alaskan SBS 3-Tab Shingles- Cut, flexed and used as capping (included)	\$503.00	<input type="checkbox"/>	or	\$5.34	*Monthly
MALARKEY E-Z Ridge SBS pre-formed high profile capping	\$503.00	<input type="checkbox"/>	or	\$5.34	*Monthly

Shingle Color: _____

Recommended Options:

In-line Dampers (Prevents heat loss/ condensation from bathroom fan vents- Only)	\$29.00 ea	<input type="checkbox"/>	Qty ()
High Rise vents (Help maintain vent performance during snow load- No moving parts) (Pre-finished steel construction- Replaces use of Turbine)	\$149.00 ea	<input type="checkbox"/>	Qty ()

Roof System includes the following Specifications :

Site protection and safety protocols to be implemented as required.

Remove existing material and haul away, # of layers: 1 Asphalt Shingles

(Extra charges will apply for hidden layers of material)

Repair roof decking @ \$2.95/sq ft, if required (minimum 1 sheet charge, plus delivery)

5-Point penetration inspection to resolve existing leaks and search for any undetected problems- Client to be advised of any issues found

1-Row 44" Ice & Water protection along eaves and in valleys.

1-Ply 54" Synthetic felt replacement underlayment on remainder of roof.

Product specific starter shingles on entire roof perimeter.

Replace (4) Attic vents- (2)New vents added to meet code/spec requirements.

Replace (2)Gooseneck vents, Replace (2)Plumbing flashings.

Product specific capping as specified above.

Caulk all roof penetrations and exposed nails.

Thorough clean out eavestroughs and work area when complete.

Subtotal: _____

5% G.S.T.: _____

Total: _____

All work is monitored and inspected throughout installation for quality and safety.

Final QC Inspection and report upon completion.

*Monthly payments based on 8.95% interest at 15 years amortization.

Financing on approval of credit. Rates subject to change.

Signature: _____

(See Terms and Conditions next page)

Above includes material and equipment containment during installation, the removal and disposal of all waste construction materials and final site cleanup upon completion.



Sample

January 10, 2017

We at Jayson Global Roofing Inc. would like to thank you for the opportunity to submit a quotation for the following roofing specifications.

Job Name: Sample Residence

Job Code: L

Job Address:

Job Number: Re-roof Existing House

Supply and Install: 6-nail install pattern

Price:

IKO Cambridge AR Laminate shingles 15/LT warranty	\$5,387.00	<input type="checkbox"/>	or	\$57.19	*Monthly
IKO Cambridge IR (impact rated) Laminate shingles 15/LT warranty	\$7,269.00	<input type="checkbox"/>	or	\$77.16	*Monthly
IKO Hip & Ridge Plus segmented fibreglass strip shingles used as capping (included)	\$429.00	<input type="checkbox"/>	or	\$4.55	*Monthly
IKO Ultra HP SBS pre-formed high profile ridge capping (manufacturer recommended)	\$429.00	<input type="checkbox"/>	or	\$4.55	*Monthly
GAF Timberline HD Laminated shingles 50/LT system plus warranty	\$5,842.00	<input type="checkbox"/>	or	\$62.02	*Monthly
GAF Timbertex SBS pre-formed mid profile ridge capping (included)	\$5,842.00	<input type="checkbox"/>	or	\$62.02	*Monthly
MALARKEY Highlander Laminate Shingles 10/30 year warranty	\$7,053.00	<input type="checkbox"/>	or	\$74.87	*Monthly
MALARKEY Legacy SBS Laminate Shingles 15/50 year warranty	\$8,015.00	<input type="checkbox"/>	or	\$85.08	*Monthly
MALARKEY E-Z Ridge SBS pre-formed high profile capping (included)	\$8,015.00	<input type="checkbox"/>	or	\$85.08	*Monthly

Shingle Color: _____

Pre-finished Valley flashing color: (Black, Brown or Charcoal)

Recommended Options:

In-line Dampers (Prevents heat loss/ condensation from bathroom fan vents- Only)	\$29.00 ea	<input type="checkbox"/>	Qty ()
High Rise vents (Help maintain vent performance during snow load- No moving parts) (Pre-finished steel construction- Replaces use of Turbine)	\$149.00 ea	<input type="checkbox"/>	Qty ()

Roof System includes the following Specifications :

Site protection and safety protocols to be implemented as required.

Remove existing material and haul away, # of layers: 1 Asphalt Shingles

(Extra charges will apply for hidden layers of material)

Repair roof decking @ \$2.95/sq ft, if required (minimum 1 sheet charge, plus delivery)

5-Point penetration inspection to resolve existing leaks and search for any undetected problems- Client to be advised of any issues found

Pre-finished Steel Drip Edge eave flashing along eave edges.

1-Row 44" Self-Adhering Ice & Water protection along eaves and in valleys.

Pre-Finished Steel W-Valley flashings(prevents granule loss and early erosion)

1-Ply #15 felt or Shinglemate paper on remainder of roof- Extends down over I&W membrane to prevent shingle embedding.

Product specific starter shingles on entire roof perimeter.

Replace (4) Attic vents- (2)New vents added to meet code/spec requirements.

Replace (2)Gooseneck vents, Replace (2)Plumbing flashings.

Product specific capping as specified above.

Caulk all roof penetrations and exposed nails.

Thorough clean out eavestroughs and work area when complete.

All work is monitored and inspected throughout installation for quality and safety.

Subtotal: _____

5% G.S.T.: _____

Total: _____

Above roofing systems achieve a CLASS-A fire rating.

Final QC Inspection and report upon completion.

Signature: _____

(See Terms and Conditions next page)

*Monthly payments based on 8.95% interest at 15 years amortization.

Financing on approval of credit. Rates subject to change.

Above includes material and equipment containment during installation, the removal and disposal of all waste construction materials and final site cleanup upon completion.